

# Technical Information Bulletin

Date: 8.01.2018

---

## **Concerning: Pre-filled gravel underbedding**

Dear Customer,

In our continuous efforts to further improve the quality of our products, we will implement the following modifications on our ProFlow range:

- 1) No Pre-fill of gravel underbedding for systems bigger than 2 Cuft:
  - Transport horizontally or vertically is possible
  - Weight & size of the system is not changing
  - No damage/movement of the riser tube
  - Delivered in buckets of max 20 kg
  
- 2) As the valve is not mounted on these systems an additional sticker "Fragile" will be added on the valve box or the pallet.

This upgrade is introduced in our production as of 1/01/2018.

Please do not hesitate to contact us if you need any additional information on this topic.



Sofie Redig  
Technical Support

